ROYALTY CALCULATION

Name of Work : Improvement to roads and drains at Bagalagunte old village Harijana colony in Ward No.14 Dasarahalli sub division

Job Code:14-20-000018 Est.Cost Rs.150.00 Lakhs

Description	Qty in Cum	Constant	Total Qty
Plain Cement Concrete 1:3:6			
Sand	76.60	0.46	35.24
Jelly	76.60	0.89	68.17
Cement Concrete M25			
Sand	312.52	0.43	134.38
Jelly	312.52	0.69	215.64
Precast Concrete Slab 100mm			
Sand	106.11	0.459	48.70
Jelly	106.11	0.88	93.16
Precast Concrete Slab 250mm			
Sand	26.27	0.43	11.30
Jelly	26.27	0.69	18.13
KERB			
Sand	1424	0.017	24.21
Jelly	1424	0.032	45.57
Cement Concrete M20			
Sand	35.55	0.43	15.29
Jelly	35.55	0.69	24.53
wet mix macadam			
Jelly	381.45	1.00	381.45
Bituminous macadam			
Jelly	111.55	1.41	157.29
Bituminous Concrete			
Jelly	278.6	1.40	390.04

Scanned with CamScanner

SSM 1:6			
Sand	23.81	0.30	7.14
Jelly	23.81	1.05	25.00

Sl	Items	Qty	Rate	Amount
1	Sand	276.26 X	138	38,124-00
2	Jelly	1418.98 X	126	1,78,791-00
			Total	2,16,915-00

Note: Only Qty is Given By Sub Division office

Asst.Engineer
Bagalagunte Ward No 14

Asst.Executive Engineer
T.Dasarahalli Sub Division

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರ
ಟಿ. ದಾಸರಹಳ್ಳಿ ಉಪ ವಿಭಾಗ
ಬಾಗಲಗುಂಟೆ. ಜಿ.ಕೆ.ಎಂ.ಪಿ
ಬೆಂಗಳೂರು ೫೬೦೦೭೩

Scanned with CamScanner